

DAIKIN INDUSTRIES, LTD.

Oil Hydraulic Equipment

Osaka Office DAIKIN Esaka Building, Tarumi-cho 3-21-3, Suita, Osaka, Japan 564-0062

TEL: 81-6-6378-8764 FAX: 81-6-6378-8738

E-mail Address: hyd_eco@daikin.co.jp Home Page: http://www.daikin.com

OIL COOLING UNIT

Use of new refrigerant R410A



FUSION TECHNOLOGY FOR CONTROL

The fusion of "hydraulic technology" and "inverter technology" achieves more advanced high-accuracy temperature regulation and energy saving performance.


Shorter delivery of a product is enabled by developing individual specifications for general purpose into menus.

Daikin aims at the production of environmentally-friendly products through energy saving efforts at production sites and reduction of waste by recycling of material.

Daikin is in pursuit of further energy saving technology and more versatile functions. In these attempts, a more advanced energy-efficient inverter "Oil Cooling Unit" 8 series was developed with the super energy-efficient technology combined with the IPM motor unique to Daikin used in air conditioners. In the hope that your machine tools operate in the optimum conditions at all times, Daikin developed Oil Cooling Unit which is supported by the excellent hybrid system. Please try Daikin's Oil Cooling Unit materializing the technical strength and our passion for providing the best technology to you.

Common

Information Principle of Oil Cooling Unit and overall system diagram



[Refrigerating cycle]

- A:Refrigerant gas is converted into compressed gas at high temperature and high pressure by a compressor so that gas can be easily cooled and liquefied by a condenser.

 B:In the condenser, the gas at high temperature and high pressure made in the compressor is cooled with air and converted into liquid at high temperature and high pressure.
- C:The pressure reduction mechanism reduces the pressure of the liquid at high temperature and high pressure and converts it into liquid at low temperature and low pressure by squeezing it so that it can be easily evaporated in a cooler.
- D:In the cooler, liquid at low temperature and low pressure made in the pressure reduction mechanism removes heat from oil, evaporates (cools oil), and is converted into gas at low temperature and low pressure.

Why machine tools require Oil Cooling Unit?

Latest machine tools needs

High-speed rotation: Improving surface roughness and accuracy

Heat is generated at headstock bearings and gears. The entire main spindle is warmed and the spindle deviates from the center of the column and the head, which results in poor accuracy. It is because there are differences in temperature among machine parts.

Oil Cooling Unit can control heat generation at the headstock, and the deviation can be corrected. Oil Cooling Unit lubricates the headstock gears and removes the heat generated. It is helpful to improve machine accuracy. (AKZ8 series)


Increased machining accuracy of work and extension of tool life

Highly accurate processing can be attained by controlling temperature of cutting and grinding fluids. In addition, longer tool life can be attained and deterioration of coolant can be reduced. Oil Cooling Unit contributes to improve machine operation efficiency. (AKZJ8 series)

Controlling oil temperature to optimum value according to heat generation of main machine


Oil Cooling Unit compressor frequency valuable control gives appropriate cooling capacity according to the heat generated on the main machine side to meet the operating condition.

The fluid temperature can be controlled accurately depending on load fluctuation from lowest to highest. Unlike the conventional non-inverter Oil Cooling Unit, the cooling capacity can be controlled in a wider range. Not only inlet fluid oil temperature control; but outlet fluid oil temperature control, return fluid oil temperature control, room temperature tuning, machine temperature tuning, and other operation modes can be selected according to the conditions of main machine.




1 OIL COOLING UNIT

AKZ Series piping system diagram



series system piping diagram



Note) 1. The area included in a frame _____i is the area to be locally prepared and installed.

2. The heater is used only on AKZJ-H.

3 OILCOOLING UNIT



Information Description of model symbols



- 1 Standard type (Basic type of Oil Cooling Unit) AKZ : High-accuracy inverter machine, circulating type Main shaft / for lubricant
 - AKZJ: High-accuracy inverter machine, immersion open type 4 Symbol of menu (B, C, E, H, T, X)
 - Cutting for cutting and grinding liquid (oil)
- 2 Nominal capacity (kW) ×10

Adopted from the numeric sequence of JIS Z 8601 (2 digits) Ex.) "14" represents the nominal capacity 1.4 kW 14, 18, 32, 35, 43, 45, 56, 90, etc.

- 3 Symbol of series (Symbol to represent model change)
- Individual specifications for general purpose are set as a menu so as to eliminate the need to design the individual specifications in each
 - case and to allow a shorter delivery of a product. * For the combination of menus, please contact us for detailed information.
- 5 Individual order symbol (Four alphanumeric characters) Non-standard type according to individual specifications not incorporated in the menu.
 - * Please consult us for special specifications (such as compliance with UL, processing for tropical region type).

Specifications of standard, menu, and non-standard types

■AKZ8 (Circulating type)

	Standard type	Menu	Non-standard	Remarks
Use of low-viscosity oil	0			Viscosity of oil for use : 1.4 — 200 mm²/S
Relief pressure : 0.5Mpa	0			Pump relief open pressure
With timer	0			99-hour timer
With outlet temperature sensor	0			
With breaker		В		
Compliance with CE		С		European Safety Standard
Different voltages (With transformer)		E*		The type "E" marked with "*" E1:AC220,230V 50/60Hz includes three voltage types (E1, E2, E3) as listed on the right. E2:AC380,400,415V 50/60Hz E3:AC440,460,480V 50/60Hz
With heater		Н		
With tank		T1,T		T1 (AKZ148·AKZ328·AKZ438), T (AKZ568,AKZ908)
Low load control		Χ		Cooling capacity control range: 0-100% (AKZ148, AKZ328, AKZ438, AKZ568) (Excluding Type H)
Relief pressure : 0.98 Mpa			0	Unit with separately installed pump
Relief pressure: 1.47 Mpa			0	Unit with separately installed pump
Use of twin pump			0	Unit with separately installed pump
Specified painting color			0	
With extension board for serial / parallel communication			SP	Standard type of AKZ148, AKZ328, AKZ438, and -C, -E*, -T* types

■AKZJ8 (Immersion type)

	Standard type	Menu	Non-standard	Remark	(S
Use of low-viscosity oil (liquid)	0			Viscosity of oil for use:	0.5 - 200 mm ² /S
With timer	0			99—hour t	timer
With breaker		В			
Compliance with CE		С		European Safet	y Standard
Different voltages (With transformer)		E*		The type "E" marked with "*" includes three voltage types (E1, E2, E3) as listed on the right.	E1:AC220,230V 50/60Hz E2:AC380,400,415V 50/60Hz E3:AC440,460,480V 50/60Hz
With heater		Н			
Specified painting color			0		
With extension board for serial / parallel communication			SP	Standard type of AKZJ188, AKZJ358	, AKZJ458, and -C, -E* types

■Optional parts (Refer to Pages 37 and 38)

- •Thermistor for machine synchronization (Lead wire length: 5m, 10m, 15m)
- •Thermistor for oil temperature control (Lead wire length: 5m, 10m)
- •Extension board for main machine communication (Šerial communication, serial / parallel communication enabled)

OILCOOLING UNIT | 4

a ZNA

OIL COOLING UNIT

AKZ8 Circulation type SERIES



AKZ8

Overview

High-accuracy type by inverter control of compressor and control by electronic expansion valve

Circulating Oil Cooling Unit (Incorporated circulating pump)

Enclosed cooler

New refrigerant R410A (Ozone Depletion Potential (ODP): 0)


Enable the temperature control in low-load zone by the increased control range of cooling capacity $\langle \text{Existing type: } 10 - 100\%, \rightarrow 8 \text{ series: } 0 - 100\% \text{ (5 - } 100\% \text{ on some types)} \rangle$

Wider operating temperature range (Room temperature: 5 - 45°C, Inlet oil temperature: 5 - 50°C)

AKZ8

Features

Achieve high energy-saving performance



*Comparison against the energy-saving performance of the existing ON / OFF type (AKS5 series) set as 100

Achieve low-noise operation

68dB (A) -> 62dB (A)


in AKZ 1.2HP class

Value equivalent as measured in an anechoic chamber

It is generally known that ordinary conversation can be conducted with a person one meter away in an environment at a noise level of 60dB (A).



Achieve high-accuracy temperature control



Inverter control maintains your machine at optimum operating conditions at all times and improves the machining accuracy of the machine.

OIL COOL ING UNIT

Extension of cooling capacity control range

■Achieve the low-load control at 0 - 100% (except AKZ908).

Assure relief pressure of 0.5Mpa as the standard

0.3Mpa on the existing type

Features

Significant solution of piping pressure loss

Use of low-viscosity pump as the standard

■Viscosity range of oil for use: 1.4 - 200 mm²/s

New convenient function in addition to the current oil temperature warning function

■Auto tuning function

Since the temperature control gain is automatically set just by operating the main machine at no load for 10 to 20 minutes, the trial run adjusting time is greatly reduced.

Refrigerant gas shortage detection function
When the refrigerant gas leak status occurs (cooling disabled), alarm signals are output. Indirectly prevent the burn of spiridle.


■99-hour timer function (ON timer)

The operation start time can be set in a range between 0 and 99 hours (Unit in hour).

Five types of menu machines in addition to the standard type enable a shorter delivery of product



Individual specifications for general purpose are set as




Compact design of top class in the industry



AKZ8

Applications



5 OIL COOLING UNIT

SERIES

Specifications (AKZ148·328·438)

Oil Cooling Unit horsepower (HP)	Т				0.5	5					1.2	2					1.5	5	
	t				AKZ1	148					AKZ	328					AKZ4	138	
Model name	Star	-в	-c	-X*3	-H	-T1 *8	-E *3	Stan _	В-	C -X*9	-H	−T1 *8	-E *3	Stan	-B-	C -X*9	-н	-T1 *8	-E *3
Cooling capacity (50/60Hz) *1 kW	Т		Т		1.3/	1.4		П			2.8/3	3.2		Г			3.8/4	1.3	
Heater kW		-	-		1	-	-		-		1	-	-		-		1	-	-
Supply power ^{*2}	Th	ree	phas	se AC	200/200•22	20V 50/60Hz	*3	Thre	e ph	nase A	C 200/200 • 22	20V 50/60Hz	*3	Th	ree ph	ase A	C 200/200 · 22	0V 50/60Hz	*3
Main circuit	Г							Thr	ee į	phas	e AC 200	/200•220V	/ 50/60Hz						
Circuit voltage Operating circuit											DC12	/24V							
200V 50Hz					1.20kV	V3.5A					1.70kV/	√5.3A					2.31kVA	V6.6A	
Max. power consumption Max. consumption current 200V 60Hz					1.32kV	V3.7A					1.73kV <i>A</i>	V5.5A					2.35kVA	V6.8A	
220V 60Hz					1.33kV/	V3.9A					1.75kV/	√5.7A					2.45kVA	V7.0A	
Transformer capacity					-		2.6kVA				-		2.6kVA				-		2.6kVA
Exterior color	Г										Whi	ite							
Outside dimensions (HXWXD) mm	65	0X3	60X4	140 95	60X360X440	820×360×465	950X360X440	790>	(360)	X440	1090×360×440	1055X360X465	1090X360X440	990	X360	X440	1290X360X440	1225X360X465	1290X360X440
Compressor (Totally enclosed DC swing type)				Eq	uivalent	to 0.4kW				Е	quivalent t	to 0.75kW				Е	quivalent	to 1.1kW	
Evaporator											Shell-end	coil type							
Condenser											Cross-fin	coil type							
Propeller fan Motor											φ300 _\	75W							
Motor											0.4kW	X4P							
Oil Theoretical discharge rate L/min	Г		П		12/1	4.4			T				24/2	28.	В				
Open pressure MPa					0.5	5		П					0	.6					
Syn- Standard	Г		П		Room to	emperatur	e or mach	ine t	em	pera	ture *4 (S	et to "Roo	om temper	ratu	ıre: N	/lode	3" by de	fault)	
Temperature zation Object to be controlled					Inle	et oil temp	erature or	outl	et c	oil ter	nperature	(Set to "I	nlet oil ter	npe	eratu	re"	by default))	
adjust type Synchronization K	Г		П			- 9.	9~+9.9	agai	nst	the s	standard to	emperatur	e (Set at 0	0.0	by de	efaul	lt)		
(Selectable) Fixed Object to be controlled							Ir	nlet o	oil te	emp	erature or	outlet oil t	emperatur	re					
type Range °C	Г		Π						T		5~:	50							
Refrigerant control						Comp	ressor rev	oluti	ons	by i	nverter +	Opening	of electric	exp	oans	ion v	alve		
Refrigerant (New refrigerant: R410A) ¹⁵ Filling amount kg	Г		Ī		0.4	9		П	T		0.7	2					0.9	8	
Protection equipment		high	rooi nder	m-ten nser t	nperature i emperatur	protection the e thermostal	ermostat, lov t, refrigerant	v oil-t leak	emp dete	eratu	re protection and inverter	thermostat, protection ed	relief valve t uipment. Hi	for p gh-p	ump, ressu	disch re sw	temperature harge tube ten vitch (—C type otection switch	mperature the only), con	ermostat, pressor
Room temperature °C	L										5~	45							
Inlet oil temperature °C	L										5~:	50							
Operating Oil viscosity mm²/s	L									1.4	~200 (ISC) VG2~32	2)						
Product external Discharge side											0.5MPa	or less							
pressure loss Suction side											−30.7kPa	a or less							
Usable oil	L	ubric	ant, I	hydrau	ilic oil of mir	neral oil (Not u	sable for hydra	aulic c	il of	ester p	hosphate, wa	ter, water-solu	ble liquid, dru	gs, fo	ood pro	oducts	, fuel, cutting li	quid, grinding	liquid, etc.)
Oil inlet	L										Rc3	/4							
Connecting tube Oil outlet		Rc	3/4	F	Rc1 1/4		Rc3/4				Rc1 1/4		Rc3/4				Rc1 1/4	Rc	3/4
Oil drain											Rc1/4 (PI	ugged)							
Noise value (Value measured at 1m high in front, value equivalent as measured in anechoic chamber) dB (A)							6	2									65	i	
Transport vibration performance						L	Jp down 1	4.7n	1/S ²	2 (1.	5G) ×2.5	hr (10~10	00Hz swee	ep /	5 m	in.)			
Mass kg		52		53	62	65	110	5	8	60	68	73	116		67		77	82	125
Molded-case circuit breaker (Rated current) A	[-	10				_		- 1	0			_		_	10				
Oil tank (Capacity)						15	_					20	_					20	_
To be prepared Molded-case circuit breaker (Rated current) A							1	0 (F	Req	uirec	for types	other than	B type)					

- Note) *1.The cooling capacity represents the value at the standard point (inlet oil temperature: 35°C, room temperature: 35°C, oil for use: ISO VG32). The tolerance of the product is approx.±5%.

 *2.Be sure to use a commercial power supply for the power source. The use of an inverter power supply may cause burn damage to the machine.

 - The voltage fluctuation range should be within ±10%. If the voltage fluctuation range is more than ±10%, please consult us.

 *3.There are three types of different voltages (-E1, -E2, -E3 types) according to the supply voltage. (Refer to Page 4 for details.)

 *4.The machine synchronization thermistor optionally available is required for this function. (Refer to Page 37 for details.)

 - *5.The MSDS (Material Safety Data Sheet) of refrigerant R410A is attached to —C type.

 *6.The molded-case circuit breaker is not supplied with this product. Please prepare it by yourself.

 *7.Existing machines of 1HP class (AKS105AK, AKZ(S) 257 class) were integrated into AKZ328 of 1.2HP class.
 - *8. The yellow line on the tank oil level gauge shows the highest oil level and the red line the lowest oil level.
 - *9. The types -X and -H cannot be selected simultaneously.

7 OILCOOLING UNIT



SERIES

Specifications (AKZ568 • 908

Oil Coolin	g Unit horsepov	ver (HP)					2.							.0			
Model na	ıme				_		AKZ	ı					ı	2908			
			Stan dard	-B -	-C -	-X* 9	-н	-T *8	-E *3	Standard	- В	- C	-н	-T *8	−E *3		
Cooling ca	apacity (50/60Hz)	1 kW					5.0/	/5.6					8.0	/9.0			
Heater		kW		_			2	-	_		-		3	-	_		
Supply po	ower*2		T	Three	pha	ase	AC 200/200 • 22	20V 50/60Hz	*3	Th	ree p	hase	AC 200/200 • 22	20V 50/60Hz	*3		
Circuit vo	Main c	ircuit						Thre	e phase AC 200	/200	•220\	V 50/6	60Hz				
Circuit vo	Operati	ng circuit							DC12	2/24V							
		0V 50Hz					3.21kV	A/9.4A					5.02kV	A/15.2A			
	r consumption 20 Imption current 20	0V 60Hz					3.30kV	A/9.5A					5.14kV	5.14kVA/15.6A			
Max. COLISU		20V 60Hz					3.34kV	A/9.2A					5.20kV	A/14.5A			
Transform	mer capacity		Т				_		5kVA				_		6kVA		
Exterior o	· '								Wh	ite							
	nensions (HXWXI) mm	111	0×470	1X5	500	1410×470×560	1375×470×580	1360×470×590		X560	X620	1520×560×680	1485×560×700	1470×560×69		
	(Totally enclosed DC			5/14/10	,,,,	,00	Equivalen		1000/14/0/1000	1220	, ,000.	, ,020		t to 2.2kW	11/0/1300/103		
		ownig type)					Lquivaiell	L LO T.ORVV	Shall and	l coil :	hypo		Lquivalen	. 10 C.CNVV			
Evaporate									Shell-end								
Condense			\vdash					01407745	Cross-fin	COII t	ype		.450 .5	-0140 / 4D			
Propeller			⊢				φ400、90	0WX4P					φ450、15	50W×4P			
Oil —	Motor		_						0.75k\								
pump _	heoretical discharge ra	te L/min							30/	36							
C	Open pressure	MPa							0.	6							
	Syn- Standa	ard				R	oom temperatur	re or machine te	mperature *4 (S	et to	"Ro	om te	mperature: Mod	de 3" by defaul	:)		
Temperature		e controlled					Inlet oil temp	erature or outle	t oil temperature	(Set	to "	Inlet	oil temperature"	by default)			
adjust	type Synchron range	ization K					-9	.9∼+9.9 again	st the standard	tempe	eratu	re (Se	et at 0.0 by defa	ult)			
(Selectable)	Fixed Object to b	e controlled						Inlet o	I temperature or	outle	et oil t	tempe	erature				
	type Range	°C							5~	·50							
Refrigera	int control		Т				Comp	ressor revolutio	ns by inverter +	- Ope	ening	of ele	ectric expansion	valve			
	refrigerant: R410A) ¹⁵ Filling a	mount ka					1.2		,					53			
Protection	n equipment		hi	gh roor conden	n-te iser	mpe tem	ent relay (motor for perature protection the perature thermostate (-C type	ermostat, low oil-te t, refrigerant leak de	mperature protection etector, and inverter	n thern protec	nostat, ction e	relief quipme	valve for pump, disc ent. High-pressure s	charge tube temper witch (-C type only	ature thermostat,		
	Room temperat	ure °C							5~	-45							
	Inlet oil tempera	ture °C							5~	-50							
Operating	Oil viscosity	mm²/s							1.4~200 (ISC) V	G2~:	32)					
range	Product external Di	scharge side							0.5MPa	or le	SS						
		ction side			Ť				─30.7kF								
Usable oi			Luh	oricant h	nydra	aulic	oil of mineral oil (Not u	usable for hydraulic oil				uble lin	uid, druas, food produc	ts, fuel, cutting liquid	arindina liquid, etc.)		
200010 01	Oil inle	et .			_		1 1/4	Rc 1	Rc 1 1/4	, 170			1 1/4	Rc 1	Rc 1 1/4		
Connecting					ť	.0 1		1101		1/4		110	, .	110 1	110 1 1/4		
Johnecilli	· —								Rc1/4 (F		24)						
Noise value (Value	Oil dra e measured at 1m high in fro						_	E	RC1/4 (F	iugge	su)			7			
	e measured at 1m high in from as measured in anechoic char						6		102 /4 50) \ / 5	h. / ·	0	00''		7			
	t vibration perfo							Jp down 14.7m/		nr (1		UUHZ	_				
Mass		kg		97	1	100	115	130	182		125		150	160	210		
	aire di brankar/Datad a	urrent) A	I – I	15				_		-	20			_			
Molded-case o	CIRCUIT Dreaker (Hateo C	ullolit) 71	$\boldsymbol{\vdash}$		_							_					
Molded-case o		L				-	-	50	-			-	_	70	-		

- Note) *1.The cooling capacity represents the value at the standard point (inlet oil temperature: 35°C, room temperature: 35°C, oil for use: ISO VG32). The tolerance of the product is approx. $\pm 5\%$.
 - *2.Be sure to use a commercial power supply for the power source. The use of an inverter power supply may cause burn damage to the machine. The voltage fluctuation range should be within ±10%. If the voltage fluctuation range is more than ±10%, please consult us.

 *3.There are three types of different voltages (-E1, -E2, -E3 types) according to the supply voltage. (Refer to Page 4 for details.)

 *4.The machine synchronization thermistor optionally available is required for this function. (Refer to Page 37 for details.)

 *5.The MSDS (Material Safety Data Sheet) of refrigerant R410A is attached to -C type.

 - *6.The molded-case circuit breaker is not supplied with this product. Please prepare it by yourself.

 *7.Existing machines of 1HP class (AKS105AK, AKZ (S) 257 class) were integrated into AKZ328 of 1.2HP class.

 *8.The yellow line on the tank oil level gauge shows the highest oil level and the red line the lowest oil level.


 - *9.The types -X and -H cannot be selected simultaneously.

Range of use


Note) 1. The mark \bigcirc shows the standard point.


2. Be sure to use the machine at the range of use specified in


(The use outside the use range may cause machine failure.)





OIL COOLING UNIT | 8











9 OILCOOLING UNIT OILCOOLING UNIT 10

Outside dimension diagram

Description Part No. Part Name Description

AKZ8

SERIES

Outside

dimension diagram

AKZ328(-B,-C)

Standard specifications

With breaker

Note) Refer to Page 4

AKZ328-H

With heater

Note) Refer to Page 4

for more details.

#

for more details.

Part No. Part Name

1 Oil inlet 2 Oil outlet 3 Oil drain

4 Control panel

6 Power supply inlet (Right / Left) φ28 Hole 7 Signal line inlet (Right / Left) φ22 Hole

δ25 Hole

2

Description Part No. Part Name

Rc1/4 Plugged

φ25 Hole

20-19

111

11 Machine faceplate

12 Instruction faceplate

15 Electric schematic diagram facep

17 Caution plate

18 Heater box

19 Heater drain 20 Air bleeder

16 Battery charge mark faceplate

Overall caution plate

Design faceplate

5 Top panel

8 Eye plate
9 Air filter

Exhaust air

⇧

Part Name

Control panel

6 Power supply inlet φ28 Hole
7 Signal line inlet φ22 Hole

1 Oil inlet

2 Oil outlet

3 Oil drain
4 Control pa

5 Top panel

8 Eye plate
9 Air filter

Exhaust air

10 Room temperature the

10 Room temperature therm

Description Part No. Part Name Description

11 Machine faceplate

12 Instruction faceplate 13 Overall caution plat

14 Design faceplate

15 Electric schematic diagram facepla 16 Battery charge mark faceplate

18 Breaker caution plate -B type only




Outside dimension diagram



With tank

Note) Refer to Page 4 for more details.





Rc3/8 Plugged
20L
HY-06T
KLA-80A
2 -

Exhaust air

Exhaust air


*The yellow line on the oil level gauge shows the highest oil level and the red line the lowest oil level.














AKZ328-E **

Note) Refer to Page 4 for more details.

4-φ12 Hole (For foundation 11 OIL COOLING UNIT

30

13(15) Rear face

(-B type only)

4-Installation hole

13 15 Rear face

11)

2

11)

Opposite side

OILCOOLING UNIT 12



Outside dimensio<u>n</u> diagram

AKZ438-T1


With tank

Note) Refer to Page 4



Design faceplate 15 Electric schematic diagram faceplat 16 Battery charge mark faceplat Caution plate 18 Tank drain c3/8 Plugged Oil tank 21 Oil level gauge*

*The yellow line on the oil level gauge shows the highest oil level and the red line the lowest oil level.




AKZ438-E **

Note) Refer to Page 4 for more details.

(900)	
	(420) 13 (5) Rear face

_					
P	art No.	Part Name	Description	Part N	No. Part Name Description
	1	Oil inlet	Rc3/4	11	1 Machine faceplate
	2	Oil outlet	Rc3/4	12	2 Instruction faceplate
	3	Oil drain	Rc1/4 Plugged	13	Overall caution plate
Ī	4	Control panel		14	4 Design faceplate
	5	Top panel		15	5 Electric schematic diagram faceplate
	6	Power supply inlet	φ28 Hole	16	Battery charge mark faceplate
	7	Signal line inlet	φ22 Hole	17	7 Caution plate
Г	8	Hanger		18	8 Transformer box
	0	Air filter			
	10	Room temperature thermistor			

Exhaust air (397) 7



AKZ8

SERIES

Outside

dimension diagram

Standard specifications

With breaker

Note) Refer to Page 4 for more details.


AKZ438(-B,-C)

13(15) Rear face

(-B type only)

AKZ438-H

With heater Note) Refer to Page 4 for more details.



Part Name

Part No. Part Name

1 Oil inlet 2 Oil outlet 3 Oil drain

4 Control panel

6 Power supply inlet (Right / Left) φ28 Hole

7 Signal line inlet (Right / Left) φ22 Hole

φ25 Hole

2

5 Top panel

8 Eye plate
9 Air filter

Exhaust air

10 Room temperature thermi

Description Part No. Part Name Description

11 Machine faceplate

12 Instruction faceplate 13 Overall caution plat

14 Design faceplate

16 Battery charge mark faceplate

Description Part No. Part Name Description

11 Machine faceplate

12 Instruction faceplate

18 Breaker caution plate -B type only


15 Electric schematic diagram facepla

13 OIL COOLING UNIT

OILCOOLING UNIT 14

Part No. Part I

1 Oil inlet
2 Oil outlet 3 Oil drain 4 Control panel



6 Power supply inlet (Right / Left) φ28 Hole


16 Battery charge mark faceplate -B type only

AKZ568(-B,-C)

Standard specifications

With breaker

Note) Refer to Page 4 for more details.



Part Name

Description Part No. Part Name

11 Machine faceplate


Rc1 1/4

Description



With heater





AKZ8 SERIES


Outside dimension diagram

AKZ568-T


With tank


Note) Refer to Page 4

19 Yellow line 50L Red line 37L



Part No	Part Name	Description	Part No.	Part Name	Description
1	Oil inlet	Rc1	11	Machine faceplate	
2	Oil outlet	Rc1 1/4	12	Instruction faceplate	
3	Oil drain	Rc1/4 Plugged	13	Overall caution plate	
4	Control panel		14	Design faceplate	
5	Electric component box cover		15	Electric schematic diagram faceplate	
6	Power supply inlet (Right / Left)	φ28 Hole	16	Tank drain	Rc3/8 Plugged
7	Signal line inlet (Right / Left)	φ22 Hole	17	Oil tank	50L
8	Eye plate	φ25 Hole	18	Oil hole-cum-air bleeder	HY-06T
9	Air filter		19	Oil level gauge*	KLA-80A
10	Room temperature thermistor		*The \	rellow line on the oil level g	auge shows the





15 OIL COOLING UNIT

OILCOOLING UNIT 16

AKZ8

SERIES

Outside

dimension diagram

Standard specifications

With breaker

Note) Refer to Page 4 for more details.

AKZ908-H

With heater

Note) Refer to Page 4

for more details.

AKZ908(-B,-C)

Part No. Part Name

Rc1 1/4

Rc1 1/4

φ25 Hole

Rc1/4 Plugged

1 Oil inlet 2 Oil outlet 3 Oil drain

8 Eye plate
9 Air filter

Exhaust air

(574)

13(15) Rear face

(17)(-B type only) (-B type only)

4-Installation hole

13(15) Rear face

4-φ12 Hole
(For foundation bolt)

22.5

NVERTER.

4 Control panel

5 Electric component box

10 Room temperature therm

Part No. Part Name

1 Oil inlet
2 Oil outlet

6 Power supply inlet φ28 Hole
7 Signal line inlet φ22 Hole

3 Oil drain 4 Control panel

8 Eye plate

10 Room temperature the

Exhaust air

6 Power supply inlet (Right / Left) φ28 Hole

7 Signal line inlet (Right / Left) φ22 Hole

(10)

(2)

Rc1 1/4

φ25 Hole

Rc1/4 Plugged

1 (3)

> 190 257

Description Part No. Part Name Description

11 Machine faceplate

12 Instruction faceplate

13 Overall caution plate

14 Design faceplate

15 Electric schematic diagram facepla

Description Part No. Part Name Description

11 Machine faceplate

12 Instruction faceplate

14 Design faceplate

15 Electric schematic diagram facepla

16 Battery charge mark faceplate

17 Heater box

18 Heater drain

Overall caution plate

16 Battery charge mark faceplate -B type only

17 Breaker caution plate -B type only

12

c3/8 Plugged





650 700	330		472	
Part No. Part Name	Description	Part No.	Part Name	Description
1 Oil inlet	Rc1 1/4	11	Machine faceplate	Dogonphon
2 Oil outlet	Rc1 1/4	12	Instruction faceplate	
3 Oil drain	Rc1/4 Plugged	13	Overall caution plate	
4 Control panel	aggod	14	Design faceplate	
5 Electric component box cover		15	Electric schematic diagram faceplate	
6 Power supply inlet	φ28 Hole	16	Battery charge mark faceplate	
7 Signal line inlet (Right / Left)	φ22 Hole	17	Transformer box	
8 Hanger				
9 Air filter				
10 Room temperature thermistor				
Exhaust air	_			
(10)	2			12
620 (10)	3			213 790

Note) *1. The hanging fitting is located below. Do not use this fitting for hanging.

 Part No.
 Part Name
 Description
 Part No.
 Part Name
 Description

 1
 Oil inlet
 Rc1
 11
 Machine faceplate

 2
 Oil outlet
 Rc1 1/4
 12
 Instruction faceplate

 3
 Oil drain
 Rc1/4 Plugged
 13
 Overall caution plate

14 Design faceplate

15 Electric schematic diagram face

18 Oil hole-cum-air bleeder HY-06T

19 Oil level gauge* KLA-80A

*The yellow line on the oil level gauge shows the highest oil level and the red line the lowest oil level.

16 Tank drain

17 Oil tank

Rc1/4 Plugged

4 Control panel

Exhaust air

 $\hat{\Box}$ (574)

5 Electric component box cove

5 Electric component box cover
6 Power supply inlet (Right / Left)

7 Signal line inlet (Right / Left)

428 Hole
7 Signal line inlet (Right / Left)

425 Hole
8 Eye plate

425 Hole
9 Air filter
10 Room temperature thermistor


17 OIL COOLING UNIT


OILCOOLING UNIT 18


SERIES

Cooling Capacity Characteristic Chart














Cooling Capacity Characteristic Chart

AKZ568 7,000 Oil temperature = 6,000 Room temperature +10℃ Cooling 5,000 Oil temperature = Room temperature Oil temperature = Room temperature −10°C capacity (W) 3,000 2,000 1,000 20 25 30 10 35 40 Room temperature (°C)



■Full line ——: When operated at 60Hz ■Dashed line - - -: When operated at 50Hz

- 1. The mark "O" shows the standard point. (Room temperature: 35°C Inlet oil temperature : 35°C Oil for use: ISO VG32)
- 2. The cooling capacity differs depending on conditions such as room temperature, inlet oil temperature, oil dynamic viscosity and other factors.

19 OIL COOLING UNIT OILCOOLING UNIT | 20

New convenient function in addition to the current oil temperature warning function

■Auto tuning function

The temperature control gain is automatically set just by operating the main machine at no load for 10 to 20 minutes; the trial run adjustment time is greatly reduced.


Refrigerant gas shortage detection function


When the refrigerant gas leak status occurs (cooling disabled), alarm signals are output. Indirectly prevents damage to the machine due to failure in cooling.

■99-hour timer function (ON timer)


The operation start time can be set in a range between 0 and 99 hours (Unit in hours).

Four types of menu-incorporating machines in addition to the standard type






Compact design of top class in the industry



AKZJ8 Applications



OIL COOLING UNIT

AKZJ8

Immersion type S E R I E S

AKZJ8 Overview

High-accuracy type by inverter control of compressor and control of electric expansion valve Immersion-type Oil Cooling Unit (Direct mount on the tank) The circulating pump is not included in the unit.


Made of stainless steel Open-type cooler

New refrigerant R410A (Ozone Depletion Potential: 0)

Wide operating temperature range (Room temperature: 5 - 45°C, Tank liquid temperature: 5 - 50°C)

AKZIO Features

Achieve high energy-saving performance



*Comparison with the energy consumption of existing ON / OFF type (AKJ series) set as 100 $\,$

Achieve low-noise operation


68dB (A) - 62dB (A)

in AKZJ 1.2HP class Value equivalent as measured


in an anechoic chamber It is generally known that ordinary conversation can be conducted with a person one meter away in an environment at a noise level of 60dB(A)



Achieve high-accuracy temperature control



New inverter type - AKZJ8 series



Note) Pattern diagram with the heating load stabilized at 30 - 100% (Comparison with Daikin product)

Inverter control maintains your machine at optimum operating conditions at all times and improves the machining accuracy of the machine.

21 OIL COOLING UNIT

SERIES

Specifications (AKZJ188 • 358 • 458)

Oil Cooling	J Unit h	orsepower (HP)			0	.5				1	.2				1	.5	
					AKZ	J188				AKZ	J358				AKZ	J458	
Model nan	ne		Standard	-в	-с	—н	-E *3	Standard	-в	-с	—н	−E *3	Standard	-в	-с	-н	-E *3
Cooling cap	acity (5	i0/60Hz)*1 kW			1.6	/1.8				3.2	/3.5				4.2	/4.5	
Heater		kW		_		1	_		_		1	_		_		1	_
Supply por	wer*2		Three p	hase AC	200/200•2	220V 50/60Hz	*3	Three p	hase AC	200/200+2	20V 50/60Hz	*3	Three p	hase AC	200/200+2	20V 50/60Hz	*3
0: : !		Main circuit						Three	phase	AC 00	/200•220V	50/60Hz					
Circuit volt	tage -	Operating circuit								DC12	2/24V						
		200V 50Hz	1.0	7kVA/3	3.1A	1.35kVA/5.7A	Same	1.7	6kVA/5	.2A	1.76kVA/5.9A	Same	1.9	4kVA/5	5.7A	1.94kVA/5.9A	Same
Max. power of Max. consum			1.0	9kVA/3	3.2A	1.35kVA/5.6A	as the standard	1.7	8kVA/5	.2A	1.78kVA/5.8A	as the standard	1.9	6kVA/5	5.7A	1.96kVA/5.8A	as the standard
IVIAA. COITSUIT	iipiioii ci	220V 60Hz	1.0	7kVA/2	2.8A	1.62kVA/6.1A	type	1.7	9kVA/4	.9A	1.79kVA/6.3A	type	1.9	8kVA/5	.3A	1.98kVA/6.3A	type
Transform	er cap	acity			_		2.2kVA			_		2.2kVA			_		2.2kVA
Exterior co	olor									Wh	nite						
Outside dime	ensions (HXWXD) mm		980×	360×4	40	980×450×630		1120×	⟨360×₄	140	1120×450×630		1320>	<360×	440	1320×450×630
Compressor (T	Totally end	closed DC swing type)		Eq	uivalen	t to 0.4kW			Equ	ivalent	to 0.75kW	,		Eq	uivalen	t to 1.1kW	
Evaporato	r									Open c	oil type						
Condense	r								С	ross-fin	coil type						
Propeller f	fan	Motor								φ300	.75W						
Agitator		Motor								1φ.50	W、4P						
	Syn-	Standard			Roor	n temperat	ure or mad	hine te	mperat	ure*4(S	Set to "Roo	m temper	ature: N	Node 3	" by de	fault)	
	chroni- ⁻ zation	Object to be controlled							Tank	liquid	temperatui	е					
	type	Synchronization K				-9	.9~+9.9 8	against	the sta	ndard t	emperatur	e (Set at 0	0.0 by c	default)			
(Selectable) -	Fixed	Object to be controlled							Tank	liquid	temperatui	e					
	type	Range °C								5~	·50						
Refrigeran	nt contr	ol				Compr	essor revo	lutions	by inve	erter +	Opening of	f electroni	c expar	nsion v	alve		
Refrigerant (New ref	frigerant: R4	10A) ¹⁵ Filling amount kg			0.	58				0.8	B1				0.	99	
Protection	equip	ment	th	nermost	at, high thermos	oil tempera tat, conden aker (-B ty	ostat, revers ture protect ser tempera pe only) Hi eat preventi	ion ther iture the gh-pres	mostat, ermosta sure sw	low oil t t, refrige itch (—(emperature erant leak de C type only)	protection etector, and , compress	thermo: l inverte or prote	stat, dis r protec ection th	charge tion equ ermost	tube tempe uipment;	rature
	Room te	emperature °C								5~	·45						
Operating range	Tank l iqu	id temperature °C								5~	·50						
	Oil vis	cosity mm ² /s								0.5~	-200						
Usable oil				Wa	iter-soli	uble cutting	ı liquid, grii (Car				il, grinding s, food pro			raulic c	oil, indu	strial wate	
Noise value (Value n value equivalent as r	measured at measured in	1m high in front, anechoic chamber) dB(A)								6	2						
		on performance					Up down 1	4.7m/S	² (1.50	G) ×2.5	hr(10~1	00Hz swee	ep / 5 m	nin.)			
Mass		kg		38		41	103		44		47	109		53		56	118
Molded-case cir	rcuit break	xer (Rated current) A	-	10		_		-	10		_		-	10		_	
	Molded-ca breaker (F	ase circuit A						0 (Rec	uired f	or types	other tha	n -B type)				
	Device oth					Tan	k (400mm	or mor	e in de	pth), si	upply pum	o, float swi	tch, ret	urn filte	r		

Note)*1. The cooling capacity represents the value at the standard point (inlet oil temperature: 35°C, room temperature: 35°C, oil for use: ISO VG32). The tolerance of the product is approx. ±5%.

*2.Always use a commercial power supply for the power source. The use of an inverter power supply may cause burn damage to the machine.

The voltage fluctuation range should be within $\pm 10\%$. If the voltage fluctuation range is more than $\pm 10\%$, please consult us.

*3.There are three types of different voltages (—E1, —E2, —E3 types) according to the supply voltage. (Refer to Page 4 for details.)

*4.The machine synchronization thermistor optionally available is required for this function. (Refer to Page 37 for details.)

*5.The MSDS (Material Safety Data Sheet) of refrigerant R410A is attached to —C type.

*6.The molded-case circuit breaker is not supplied with this product. Please prepare it by yourself.

*7.Existing machines of 1HP class (AKJ106, AKZJ287 class) were integrated into AKZJ358 of 1.2HP class.





Specifications (AKZJ568 • 908

Oil Cooling Unit horse	power (HP)				2.0			3.0						
Model name					AKZJ568					AKZJ908				
Wodername		Standard	-В	-с	-н	—E *3	Standard	-В	-c	-н	-E *3			
Cooling capacity (50/60	Hz)*1 kW				5.0/5.6					8.0/9.0				
Heater	kW		_		2	-		_		4	_			
Supply power*2		Three	phase A	C 200/2	00·220V 50/60Hz	*3	Three	ohase A	C 200/20	00·220V 50/60Hz	*3			
Circuit voltage Mai	n circuit					Three phase AC 200/2	200 • 220 V 50/60 F		z					
Ope Ope	rating circuit					DC12	2/24V							
Mary	200V 50Hz	3.3kVA/9.4A		1A	4.0kVA/11.4A		3.9	kVA/11.	2A	7.5kVA/21.6A				
Max. power consumption Max. consumption current	200V 60Hz	3.3kVA/9.4A		1A	4.0kVA/11.4A	Same as the standard type	4.1	kVA/11.	7 A	7.5kVA/21.6A	Same as the standard type			
,	220V 60Hz	3.4	4kVA/9.0	OΑ	4.8kVA/12.5A	4.3kVA/11.2		2A	9.0kVA/23.7A	, , , , , , , , , , , , , , , , , , , ,				
Transformer capacity	/			-	-	5kVA			-	-	6kVA			
Exterior color						Wh	nite							
Outside dimensions (HXV	VXD) mm			1450×4	70×500	1450×560×710			1630×5	60×620	1630×655×830			
Compressor (Totally enclosed	DC swing type)			Equ	ivalent to 1.5kW				Equ	ivalent to 2.2kW				
Evaporator						Open o	oil type							
Condenser						Cross-fin	coil type	9						
Propeller fan Mot	tor			¢	400、90W×4P				φ	450、150W×4P				
Agitator Mot	tor					1¢.50	W、4P							
	ndard		F	Room ter	nperature or machi	ne temperature*4 (S	Set to "R	oom ten	perature	e: Mode 3" by defa	ult)			
chroni- Temperature zation Object	ct to be controlled					Tank liquid	tempera	ure						
adjust type Sync	hronization K				−9.9∼+9.9 ag	ainst the standard t	emperat	ure (Se	t at 0.0 b	y default)				
(Selectable) Fixed Object	ct to be controlled					Tank liquid	tempera	ure						
type Rar	nge °C					5~	-50							
Refrigerant control					Compressor revolu	tions by inverter +	Opening	of elect	ronic ex	pansion valve				
Refrigerant (New refrigerant: R410A) 15 F	illing amount kg				1.25					1.65				
Protection equipmen		rooi	m tempe charge tu equip	rature pro ube temp oment; ar	ner thermostat, agitat stection thermostat, he erature thermostat, c ad non-fuse breaker (-C type only), overhe	igh oil temperature p ondenser temperatur —B type only) High-	rotection e thermo pressure	thermost stat, refr switch (-	at, low oil igerant le -C type o	temperature protect ak detector, and inve nly), compressor pr	tion thermostat, erter protection otection			
Room tempe	erature °C					5~	45							
Operating Tank liquid ter	mperature °C					5~	-50							
Oil viscosit	y mm²/s					0.5~	-200							
Usable oil			Water	-soluble	cutting liquid, grind (Cann	ing liquid, cutting o ot be used for drug					rial water			
Noise value (Value measured at 1m high value equivalent as measured in anechoi	in front, ic chamber) dB(A)				65					68				
Transport vibration pe					Up down 14.	7m/S² (1.5G) ×2.5	hr (10~	100Hz	sweep / s	5 min.)				
Mass	kg		83		86	160		132		140	220			
Molded-case circuit breaker (Ra	ated current) A	_	15		_		_	20		_				
To be Molded-case circ	cuit A		15 (Re	quired fo	r types other than	-B type)	20 (Required	for types other	than -B type)	30	20			
prepared locally Device other that molded-case circ						r more in depth), si		41	ما مقاد در م	untille u				

Note)*1 The cooling capacity represents the value at the standard point (inlet oil temperature: 35°C, room temperature: 35°C, oil for use: ISO VG32). The tolerance of the product is approx. ±5%.

- *2 Always use a commercial power supply for the power source. The use of an inverter power supply may cause burn damage to the machine. The voltage fluctuation range should be within $\pm 10\%$. If the voltage fluctuation range is more than $\pm 10\%$, please consult us.
- *3 There are three types of different voltages (—E1, —E2, —E3 types) according to the supply voltage. (Refer to Page 4 for details.)


 *4 The machine synchronization thermistor optionally available is required for this function. (Refer to Page 37 for details.)

 *5 The MSDS (Material Safety Data Sheet) of refrigerant R410A is attached to —C type.
- *6 The molded-case circuit breaker is not supplied with this product. Please prepare it by yourself.
- *7 Existing machines of 1HP class (AKJ106AK, AKZJ287 class) were integrated into AKZJ358 of 1.2HP class.


Range of use

Note) 1. The mark $\ \ \bigcirc$ shows the standard point.

2. Always use the machine in the range of use specified above in $(\mbox{Operation of the machine outside the use range may cause machine failure.}) \label{eq:operation}$




23 OIL COOLING UNIT OIL COOLING UNIT | 24




25 OIL COOLING UNIT OIL COOLING UNIT 26


AKZJ 8 series

Outside






OIL COOLING UNIT




AKZJ 8 series Outside

imension diagram



OIL COOLING UNIT



OILCOOLING UNIT 30

AKZJ 8 ser

Outside



AKZJ568-E *

SERIES


Outside

dimension diagram

Different voltages (With transformer


Note) Refer to Page 4 for more details.

Tank bottom surface



Legs on the rear (two legs on the left and right)

Note) *1. The hanging fitting is located below. Do not use this fitting for hanging.



10

Suction

Lowest liquid level

5


2

Tank bottom surface

31 OIL COOLING UNIT 32


Outside dimension dia

AKZJ 8 series





Note) Refer to Page 4 for more details.



OILCOOLING UNIT

AKZJ 8 series

Outside

dimension diagram

Note) *1. The hanging fitting is located below. Do not use this fitting for hanging.




Outside dimension diagram

AKZJ908-E


Different voltage


Note) Refer to Page 4 for more details.




33 OILCOOLING UNIT OIL COOLING UNIT | 34

Cooling Capacity Characteristic Chart









35 OIL COOLING UNIT





Cooling Capacity Characteristic Chart





■Full line ——: When operated at 60Hz ■Dashed line - - -: When operated at 50Hz

- 1. The mark "O" shows the standard point. (Room temperature: 35°C Tank liquid temperature: 35°C Oil for use: ISO VG32)
- 2. The cooling capacity differs depending on conditions such as room temperature, tank liquid temperature, oil dynamic viscosity and other factors.

Optional

Thermistor (Compatible with all types of Oil Cooling Unit 8 series)


■Thermistor models and applications

When this optional part is installed in the oil piping of the main machine, the thermistor detects the temperature to allow the control of oil temperature.

Name	Model	Length of lead wire L(m)	Shape	Application (To be installed) by you	Applicable Oil Cooling Unit model
Therm	AKZ 8-OP-K5	5m	Ring tongue terminal DB619-121 or its equivalent 1 • 25-3	For machine synchronization	
nistor for	AKZ 8-OP-K10	10m	27.5	control / Implanted in the main	
machine	AKZ 8-OP-K15	15m	R1/8 (c) Lead wire	\machine body/	AKZ 8 Series AKZJ 8
Thermistor for machine body synchronization	AKZ 8-OP-A5	5m	DB619-122 or its equivalent L Ring tongue terminal 1·25-3	For machine synchronization control	Series
ronization	AKZ 8-OP-A10	10m	Lead wire	Attached to the surface of main machine body	
Thermistor oil temperature	AKZ 8-OP-Y5	5m	DB619-121 or its equivalent XHP-3 (Blue) SXH-001T-0.6	For return oil temperature control	AKZ 8
stor for ure control	AKZ 8-OP-Y10	10m	R1/B Lead wire	/ Installed in oil tube of the main machine/	Series

Thermistor characteristics: Resistance value \cdots R25 (Resistance value at 25°C) = 20k Ω , Tolerance: \pm 2%

Instruction for installation and connection



Optional part



Extension board for main machine communication


The following functions are enabled by mounting this option board on the Oil Cooling Unit and connecting it to the main machine:

- 1. The operation mode and the operation setting can be changed from the main machine side.
- 2. The alarm code and temperature data (machine temperature, room temperature, inlet oil temperature, outlet oil temperature, inlet and outlet differential temperature, inverter frequency) of Oil Cooling Unit can be read from the main machine side.


Communication method	Model	Installation position	Applicable model	Specification sheet No.	
Serial communication AKZ8-OP-CS		Upper face of Oil Cooling Unit control board	AKZ148、AKZ328、AKZ438、 AKZJ188、AKZJ358、AKZJ458	SS08303	
only		Rear face of front plate of Oil Cooling Unit electric component box	AKZ568、AKZ908、AKZJ568、AKZJ908		
Serial communication or parallel communication	AKZ8-OP-CSP	Rear face of front plate of Oil Cooling Unit electric component box	AKZ568、AKZ908、 AKZJ568、AKZJ908	SS08370	

- Note) 1. AKZ8-OP-CSP cannot be used with types -B and -H of AKZ148, AKZ328 and AKZ438, and types -B and -H of AKZJ188, AKZJ358 and AKZJ458, respectively
- 2. It is difficult to use the optional part AKZ8-OP-CSP with the standard type and types -C, -E and -T of AKZ148, AKZ 328 and AKZ 438, and the standard type and types -C and -E of AKZJ188, AKZJ358 and AKZJ458. Please select a non-standard type with the suffix "-SP" for use with these Oil Cooling Unit types
- 3. AKZ8-OP-CS and AKZ8-OP-CSP cannot be used with -X type of AKZ148, AKZ328 AKZ438, and AKZ568, respectively.
- 4. Refer to the specifications sheet for the communication procedure and specifications.

Installation position for AKZ8-OP-CS (serial communication only)




lead wire on the control board •Dimensions of communication board $(W \times H)$: 40×50 •The communication board is secured at four positions by locking support.



•Connect the D-SUB 9 pin connector to the RS232C support of a computer or the main machine

(A male connector is not supplied with the unit.)

■Installation position in the case of AKZ8-OP-CSP (Serial / Parallel communication)



OIL COOLING UNIT | 38

Operation mode and setting method

Mode No.	Mode name	Mode name Description		Necessary optional part
Mode 0	Inlet oil temperature, fixed temperature control	Keep the inlet oil temperature at the setting temperature within the range specified in the right column.	5~50℃	
Mode 1	Outlet oil temperature or return oil temperature control Fixed temperature control	Keep the outlet oil temperature or return oil temperature at the setting temperature within the range specified in the right column.	5~50℃	Oil temperature control thermistor (When return oil temperature is controlled)
Mode 3	Inlet oil temperature, room temperature synchronization control	Keep the inlet oil temperature at the setting temperature within the range specified in the right column.	Between Room temperature -9.9°C and Room temperature + 9.9°C	
Mode 4	Inlet oil temperature, machine temperature synchronization control	Keep the inlet oil temperature at the setting temperature within the range specified in the right column.	Between Machine temperature -9.9°C and Machine temperature+ 9.9°C	Machine synchronization thermistor
Mode 5	Outlet oil temperature or return oil temperature control Room temperature control	Keep the outlet oil temperature or return oil temperature at the setting temperature within the range specified in the right column.	Between Room temperature -9.9°C and Room temperature + 9.9°C	Oil temperature control thermistor (When return oil temperature is controlled)
Mode 6	Outlet oil temperature or return oil temperature control Machine temperature synchronization control	Keep the outlet oil temperature or return oil temperature at the setting temperature within the range specified in the right column.	Between Machine temperature -9.9°C and Machine temperature + 9.9°C	Oil temperature control thermistor (When return of temperature is controlled) Machine synchronization thermistor

Note) 1. Modes 2, 7, and 8 cannot be used on this series. Note) 2. Refer to Page 37 for details of necessary optional parts.


AKZJ 8 Series						
Mode No.	Mode name	Description	Setting temperature range	Necessary optional part		
Mode 0	Tank liquid temperature, fixed temperature control	Koon the tank liquid temperature	5~50℃			
Mode 3	Tank liquid temperature, room temperature synchronization control	Keep the tank liquid temperature at the setting temperature within the range specified in the right	Between Room temperature -9.9°C and Room temperature + 9.9°C			
Mode 4	Tank liquid temperature, machine temperature synchronization control	column.	Between Machine temperature -9.9°C and Machine temperature + 9.9°C	Machine synchronization thermistor		

Note) 1. Mode 1, 2, and 5 through 8 cannot be used on this series. Note) 2. Refer to Page 37 for details of required optional parts.

■Setting procedure: Common to AKZ and AKZJ


Default setting: Set to "Mode: 3" and temperature to "0.0". When you use your machine at a setting other than the default setting, change the setting following the procedure shown below.

- 1 Power ON --- Release the operation lock mode before starting operation for the first time. Hold down the ⋈ key and ⋈ key simultaneously for more than 2 seconds.
- 2 Select the "Setting" mode and press the key once.



7 To return to the "Normal" mode, press the 2 key three times.

Part names, functions and operation of control panel




NO.	Item	Description
1	Power lamp (Green)	The lamp is turned on while power is supplied.
2	Error warning lamp (Red)	When an error occurs: Level 1 alarm: The lamp keeps blinking Level 2 alarm: The lamp is turned on
3	Timer mode lamp (Green)	The lamp keeps blinking while the machine is at a stop in the timer mode.
4	Operation mode display	Displays the mode of the control panel. NORMAL: Normal mode SETTING: Operation setting mode MONITOR: Monitor mode TIMER: Timer setting mode
(5)	Operation mode / Data No. display	Displays the current operation mode (Normal mode, Operation setting mode) or data number of the data currently displayed on the data display part.
6	Data display	Displays various data. The data displayed differs depending on the operation mode and data number.
7	[SEL] (Select) key	Selects the operation mode.
8	[DOWN] key	Reduces the value of the operation mode, data number, and data.
9	[UP] key	Increases the value of the operation mode, data number, and data.
10	[ENT] (Determine) key	Determines the operation mode, data number, and data to be changed.

■Operation for change to each mode

A mode can be changed by operating the key in general.

To enter a special mode, hold down a number of keys in combination for more than two seconds.



Differential temperature: 0.0 (K)

■ The default setting for operation on the standard machine is:

Operation mode: 3 (Room temperature synchronization, inlet oil temperature control)

CAUTION

39 OIL COOLING UNIT

OILCOOLING UNIT 40

Note) 1. When a thermistor 2. Refer to the electric

272 (b)

SW1
Operational error

al lamp

| S LED3

Sommunication processing

AKZ8 • AKZJ8 series | Electric Wiring Connection Instruction Diagram

1 Power supply capacity ··· Refer to the max, power consumption and max, consumption current of the specification sheet of each type.

⊕ L1 L2 L3

 \otimes \otimes \otimes \otimes

L1 L2 L3

DANGER

CAUTION

Standard 60335-1).

with the control board or others.

Connect the lines to the terminals corresponding to the main power supply

1. Always install a molded case circuit breaker (to be prepared by you) of the specified capacity on the main power supply.

2. Always ground the machine. Since a noise filter is installed, there

3. Before opening the electric component box, always turn off the power,

and wait for 5 minutes until internal high voltage has been discharged.

1. To avoid the effects of noise, connect the power wire by cutting it

to the proper length so that no excess wire comes into contact

2. To perform remote control, remove the short-circuit wire between [10] and [11] and install an operation switch (to be prepared by you). 3. The mode is set to "Lock mode (Stop mode)" by default. Before starting

operation, follow the procedure to release the Lock mode from the operation

4. The machine is provided with a tamper-proof switch (SW1) to reject

make the necessary setting referring to the operation manual.

5. The CE-compliance type (-C) is categorized into the overvoltage

· Install a main power circuit breaker required according to

the following instructions in installing the -C type machine.

EN60204-1 on the main machine control panel.

category II as an auxiliary machine of the main machine. Observe

· Supply the power through the transformer provided with basic

* Basic insulation: Insulation provided on a live part to assure basic protection against an electric shock (According to IEC

the setting from the operation panel. If you want to use this function,

panel. Refer to the operation manual for the unlocking procedure.

4. Do not energize the equipment with the electric component box

is a risk of electrical shock without proper grounding.


2 Connection to power supply terminal block (X1M, Tr)

- (1) In the case of the standard type and menu-incorporating type (-B,-C,-H,-T), connect the line to X1M,
- (2) In the case of the menu-incorporating type (with transformer: -E1, -E2, -E3), connect the line to the terminal block supplied with the transformer.
- 1.Screw terminal and wiring diameter

Series	Screw	Wiring diameter			
Series	termina l	JIS cable	IEC cable	UL cable	
AKZ 148,328,438,568 AKZJ188,358,458,568	M4	2.0mm ² or more	2.5mm ² or more	AWG [#] 14 or more	
AKZ908,AKZJ908	M5	3.5mm² or more	4.0mm ² or more	AWG [#] 12 or more	

- 2. Use a round crimp-style terminal for connection.
- 3. The terminal block is for three poles and the earth wire is to be secured on the enclosure with a screw

3 Connection to signal terminal block (X2M)



Screw	Wiring diameter					
terminal	JIS cable	IEC cable	UL cable			
M3	0.25mm ² ~1.25mm ²	0.3mm ² ~1.5mm ²	AWG [#] 22 ~ [#] 16			

- 3. Use stranded wires for electric connection.
- 4. The wiring size is 0.5mm²~1.5mm² in the case of duplex

1. Screw terminal and wiring diameter

Screw	Wiring diameter					
ermina l	JIS cable	IEC cable	UL cable			
МЗ	0.25mm ² ~1.25mm ²	0.3mm ² ~1.5mm ²	AWG [#] 22 ~ [#] 16			

- 2. Use a round crimp-style terminal for connection.
- cable according to IEC.

4 Signal output time chart

(1) Operation and alarm status output

Level 1 Level 2 Power failure Level 2 (Power OFF Signal output Normal ("a" contact) 60-61 Error / Stop (Power OFF) ("b" contact 60-63 Error level ("a" contact) 60-64 Pump or agitator operation ("a" contact) 61-62

(2) Temperature range warning (Oil temperature warning) status output ... Setting change is required to enable this function.

	Operation status		Temperature range check status								
			Within the setting range			Out of the setting range					
	Signal output		_	Operation Normal	Level 1 error or Lock	Level 2 error	Power failure (Power OFF)		Level 1 error or Lock	Level 2 error	Power failure (Power OFF)
	Temperature range normal ("a" contact)	66-67	ON OFF								
_			UFF								



CAUTION 1. The following electric wires can be used on the terminal 3. For [10] to [13], please prepare contacts to meet the block for the round crimp-style terminal (1.25-3): Single wire: $\phi 0.57 \sim \phi 1.44$ (AWG#22 \sim #16)

2. Load applicable to [60 - 64] and [66 - 67] is as follows: Min. applicable load: 10mV DC, 10μ A or more

Max. applicable load: 30V DC, 2A (Resistance load)

condition of minimum applicable load 12V DC and

Stranded wire: 0.25mm²~1.25mm² (AWG#22~16) 4. When the length of the thermistor to be connected to [30] — [31] is longer than 10m, or the wiring is routed in a poor noise environment, use shielded

Supporting information



Notes for installing piping outside the machine

If the external pressure loss (site piping resistance) exceeds the specified use range, there may occur phenomena such as abnormal noise of the pump (relief noise, noise of cavitation), decrease of cooling capacity and control failure of oil temperature. Keep the external pressure loss within the specified use range.

1. Suction-side piping

Keep the suction vacuum pressure within the range between -30.7 and 0kPa. The use of a suction filter of 100 to 150 mesh is


- 2. Discharge-side piping
- Keep the pressure loss of the discharge-side piping at 0.5Mpa or less.
- 3. Do not install a stop valve on the suction or discharge side. When a stop valve must be installed on the discharge side out of necessity, use a 0.5Mpa relief valve along with the stop valve.
- 4. Calculation of piping resistance Determine the oil piping size by calculating the piping resistance according to the following equation:

Piping resistance $\triangle P=0.595 \times \nu \times Q \times L/D^4$ (For use of general hydraulic oil and lubricant)

- △ P: Piping resistance (MPa)
- ν: Dynamic coefficient of viscosity (mm²/s) -Refer to the Viscosity / Temperature Chart.
- Q: Flow rate (L/min)
- L: Piping length (m)
- D: Internal piping diameter (mm)

■Relation between oil flow rate of Oil Cooling Unit and external pressure loss

AKZ8 series Oil Cooling Unit incorporating a pump of the circulating type has the properties shown below. When the external pressure loss (\triangle p) is 0.5 Mpa or less, the rated flow rate (Q0) is achieved, but when the external pressure exceeds 0.5 Mpa, the oil flow rate becomes lower than the




Note) When the valve on the main machine side is open fully, the outlet pressure is 0.65Mpa on AKZ148, and 0.75Mpa on AKZ328, 438, 568, and 908. Design the site piping so as to have a pressure resistance higher than the respective outlet pressure.

C: Status when the external pressure loss is large and the oil flow rate is "0".

ISO VG32 Oil

ISO VG32 Oil

■Viscosity / Temperature Chart



43 OIL COOLING UNIT

OIL COOLING UNIT | 44

Notes for handling

Important notes to be observed regarding the main machine side (machine tools and industrial machine)

- 1. When adverse transport conditions are expected in transporting the machine overseas or elsewhere, special precautions should be taken in the packaging and transportation method so as to avoid the application of excessive force on Oil Cooling Unit (this machine).
- 2. Oil Cooling Unit (this machine) does not incorporate a flow switch for checking the oil supply and a temperature switch for abnormal supply of oil temperature (high temperature or low temperature). So, please provide a protection device such as a flow switch and a temperature switch on the main machine side.

Notes for operation and cooling capacity

- 1. Do not use Oil Cooling Unit for cooling a liquid at 50°C or more. Start to operate Oil Cooling Unit at the same time as the main machine or before liquid temperature rises to 40°C.
- 2. Do not place an object that hinders ventilation within 500mm of the suction port or discharge port.
- 3. If the air filter is clogged, the cooling capacity is reduced. Clean the air filter (wash with hot water or clean with air) periodically once every two weeks to prevent clogging.
- 4. If cutting powder and debris deposit and adhere to the cooling coil (evaporator) in the AKZJ8 series, the cooling capacity is reduced and failure may be caused. To avoid the adherence of deposit on the cooling coil. install an efficient return filter on the return side (liquid inlet) of the tank and periodically clean the tank inside.

Notes regarding liquid usable with Oil Cooling Unit

- 1. Liquid usable with Oil Cooling Unit is listed in the table below for each series. (O···usable, X···Not usable)
- 2. Do not use the liquid listed below as "not usable" (Marked with " \times ").

	Description	AKZ8 Series	AKZJ8 Series
Lubricant Mineral hydraulic oil	•The third class petroleum and fourth class petroleum of the fourth group hazardous materials specified according to the Fire Defense Law, and oil equivalent to discoloration No. 1 according to the copper corrosion test method (JIS K2513) of petroleum products •Oil equivalent to NAS 10 level according to the pollution level		
Nonflammable hydraulic oil Ester phosphate series Chlorinated hydrocarbon series Water - Glycol series W-O & O/W emulsion series (High-aqueous hydraulic oil)		×	×
Coolant fluid Water-soluble cutting and grinding liquid Non water-soluble cutting and grinding oil		×	0
Ethylene glycol (Antifreeze liquid)	Liquid not including an ingredient to cause the material SUS304 of the	×	0
Water (Industrial water)	cooling coil (evaporator) to corrode	×	0
Inflammable liquid like fuel	Liquid equivalent to special flammables, alcohol, first class petroleum and second class petroleum of the fourth group hazardous materials specified according to the Fire Defense Law	×	×
Drugs		×	×
Liquid for food products	Drinking water, water for cooling food products, etc.	×	×

OILCOOLING UNIT

Supporting information

Notes for handling

* Before operating this equipment, read and understand the operation manual supplied with the equipment.

Instructions for safe operation

(Signs and Instructions)

- \(\int\) DANGER. \(\cdot\) Failure to observe the instruction may cause an imminent hazardous situation that may result in personal death or serious injury.
- ⚠ WARNING ··· Failure to observe the instruction may result in personal death or serious injury.

1) General instructions

- DANGER 1 ① Use the equipment only in accordance with the intended specifications (specified in brochure, specification sheet, operation manual, caution plate).
- [! DANGER] ② Never operate the equipment in an explosive atmosphere
- [/ DANGER] ③ Do not disassemble, repair or modify the equipment by yourself.
- Defense Law, JIS B 8361 Guidelines of Hydraulic System).
- [/NWARNING] 5 Caution in the event of refrigerant leak
 - ·Ventilate a room adequately (to avoid the risk of suffocation).
 - Avoid direct contact of the refrigerant with skin (to avoid the risk of frost injury).
 - In the event of inhalation of a great deal of refrigerant, contact with skin, and refrigerant in the eye, seek medical attention immediately.
- [/ WARNING] 6 In the event of an abnormal condition, stop operation promptly, investigate the cause of the problem and take appropriate remedial measures.
- [ACAUTION] To not operate the equipment in a special environment (in a place at high temperature, high humidity, in the presence of a great deal of dirt, dust, powder dust, steam, and oil mist).
- [ACAUTION] ® Install a flow switch and temperature switch on the main machine to protect the main shaft and others.
- [(CAUTION] 9 Do not get on the equipment or place an object on the equipment.

2 Instructions for transportation

- [NDANGER] ① When hoisting the equipment, check its weight and use the eye plates and hangers on the equipment properly.
- [\(\text{WARNING} \) ② Do not get approach the equipment while it is being hoisted and moved.
- [ACAUTION] ③ When moving the equipment, take appropriate measures for fall prevention.
- [(CAUTION] 4 Do not tilt the equipment 30 degrees or more while transporting the equipment (including during storage).

3 Instructions for installation

- [MARNING] ① Install the equipment on a rigid, level foundation and secure it appropriately.
- [/ CAUTION] ② Do not place an object near the suction port and discharge port of the equipment.

4 Instructions for wiring and piping installation

- [/\DANGER] ① Wiring and piping installation should be performed by a person with specialized knowledge and skills.
- [\(\triangle DANGER \)] ② Always use a commercial power supply for the power source. (The use of an inverter power supply may cause burn damage).
- [\ DANGER] 3 Connect the wiring for power supply in accordance with the electric wiring instruction diagram of the specification sheet and operation manual.
- [!\ DANGER] 4 Ground the equipment properly.
- [\(\triangle \) WARNING \(\triangle \) Install the wiring in accordance with the standard by checking the electric schematic diagram.
- [\(\)\CAUTION \(\) \(\) Check to see that the oil piping has the pressure resistance of 1MPa or more and install the piping appropriately.

5 Instructions for trial run

- [ACAUTION] ① Check to see that the main machine is in a safe status (not activated) before starting the trial run.
- [\ CAUTION] @ Check to see that the oil piping and electric wiring are correctly connected to the main machine and that there is no looseness in connections and joints.
- [/\CAUTION] 3 Disable the operation lock of the equipment (Oil Cooling Unit) before starting the main machine.
- [ACAUTION] 4 Check to see that the required amount of oil is in the oil piping system and that the piping is not blocked in the middle.

6 Instructions during operation

- [\(\text{DANGER} \) ① Do not splash water or liquid on the equipment.
- [MARNING] ② Do not push your finger or an object into gaps of the equipment.
- [ACAUTION] 3 Do not touch the heated exhaust port of the equipment.

7 Instructions for maintenance and inspection

- [\(\) DANGER \(\) ① Perform maintenance and inspection with the equipment kept open. Working in a closed status may result in suffocation due to the leak of refrigerant.
- [/ DANGER] ② Always turn off the main power supply before starting maintenance and inspection.
- [/\DANGER] 3 Wait for five minutes after turning off the main power supply and start maintenance and inspection operation.
- [/NDANGER] @ Do not operate the equipment with the cover of the equipment opened.
- [ACAUTION] (5) Wear protective gear such as gloves and an eye protector when performing maintenance, inspection and cleaning.
- [CAUTION] 6 Clean the air filter periodically (once every two weeks in general).

45 OIL COOLING UNIT


OIL COOLING UNIT | 46

3. Three methods are shown below as a guide for estimating the heat release value from the machine tool. For determining the heat release value eventually, it is necessary to conduct tests and determine the exact heat release value for selecting appropriate Oil Cooling Unit.

•Calculation method of heat release value from main machine for the selection of appropriate Oil Cooling Unit (as a general guide)

(1) In the case of cooling of main shaft of machining center

• Method 1: To estimate the heat release value from the temperature difference between the supply oil and return oil



Q=2.778×10-7Cp•γ•Vs•△T

Q : Heat release value (kW)

Cp: Constant pressure specific heat (J/kg°C) · · · 1967.4J/kg°C


γ : Weight volume ratio (kg/m³) · · · 876kg/m³

Vs : Oil flow rate (m3/h)

 $\triangle T$: Temperature difference (°C) ··· T₂—T₁

E.g.) When "Vs" is 18m³/h (30L/min) and "△T" is 5°C $Q = 2.778 \times 10^{-7} \times 1967.4 \times 876 \times 1.8 \times 5$ =0.479×1.8×5≒4.3kW

• Method 2: To estimate the heat release value from the increase rate of oil temperature in the tank



Find the maximum gradient of oil temperature increase

To find the maximum gradient of the oil temperature, it is necessary to measure △t every one minute during the first 10 minutes.

Q=2.778×10-7Cp·y·V·△t/H

Q: Heat release value (kW)

Cp: Constant pressure specific heat (J/kg°C) · · · 1967.4J/kg°C

γ : Weight volume ratio (kg/m³) · · · 876kg/m³


V : Total oil quantity (m³)

 $\triangle t$: Temperature difference (°C) ··· t₁—t₂

E.g.) When the total oil quantity is 300L (0.3m³) and "△t" is 10°C.

 $Q = 2.778 \times 10^{-7} \times 1967.4 \times 876 \times 0.3 \times 10^{-1}$ =0.479×0.3×10≒1.4kW

• Method 3: When motor output loss is considered to be the heat release value



Q: Heat release value (kW)

H: Motor output (kW) ... For driving the main shaft

 η : Motor output loss (%)

E.g.) When the output loss is 30% for the motor output 7.5 kW \rightarrow The output loss is 30% or so in general (Cooling of main shaft head)

Supporting information

Method of selection of Oil Cooling Unit

(2) In the case of cooling of cutting and grinding liquid

- 1. The heat release value from the cutting and grinding liquid system should be roughly estimated according to the following formula as the tank capacity and pump flow rate are generally large. After rough estimation, the heat release value should be determined through conducting tests on the actual machine for selecting Oil Cooling Unit.
- 2. Formula for rough calculation of heat release value

 $Q = Q_1 + Q_2 + Q_3$

Q : Heat load of the entire machine tool system

Q1: Heat value for machining by machine tool

Q2 : Heat release value of pump motor for coolant pump (Heat transfer quantity to coolant liquid)

: Q₂=Pump motor output (kW) $\times \frac{\eta}{100}$

Q3: Heat balance between coolant liquid and room temperature via coolant tank


Q3=K·A·△T K: Heat transfer coefficient (W /m²·°C) , K=11.6~23.2 in general

A: Surface area of tank moistened surface (m²)

△T: Room temperature—Controlled liquid temperature in tank (°C)

3. Refer to Page 47 and determine the heat release value according to Method 1 or Method 2.

General guide for heat generation



E.g.) In the diagram above,

When Q₁=1.2kW

 $Q_2=(2.2+2.2+3.7)\times\frac{50}{100}$ \rightleftharpoons 4.1kW (In the case of coolant pump, " η " is 50% in general.)

 $Q_3 = 20 \times 4 \times (35 - 25) / 1000 = 0.9 \text{kW}$

 $\therefore Q = Q_1 + Q_2 + Q_3$

=1.2+4.1+0.9

=6.2kW

Supporting information

Compliance of Oil Cooling Unit with Law Concerning the Recovery and Destruction of Fluorocarbons

- ◆ Daikin Group takes positive action for global environment conservation.
- Daikin takes prompt actions for the recovery and destruction of fluorocarbons by the development of the Daikin fluorocarbon recovery, transport, and destruction system throughout the nationwide network.
- ◆ For inquiries and requests for recovery of fluorocarbons, please contact the Daikin Contact Centre open 24 hours.

The Law Concerning the Recovery and Destruction of Fluorocarbons has been in force since April 1, 2002. This Law is intended to protect the ozone layer and prevent global warming and stipulates the obligation of recovery and destruction of fluorocarbons by a business owner using the product.

The "specified products" according to the Law are categorized into Type 1 (Freezing machines and air conditioners for business use) and Type 2 (Car air conditioners). Oil Cooling Unit falls under the category of "Other devices used for freezing machines" of Type 1 according to the intent of the Law. According to this classification, every type of Oil Cooling Unit is subject to the application of the Law, whether it is newly installed or installed in the past, and regardless of the types of refrigerant for use (existing refrigerant R22 or new refrigerant R407C, R410A).

The Law obligates each business owner (user of Oil Cooling Unit) to comply with the Law. Please note that a violator of the law will face a maximum of one year imprisonment or a fine of up to 500,000 yen.


1 It is prohibited to release CFC (Fluorocarbon) into the Obligations of customer atmosphere from Oil Cooling Unit (this product). Specifically, the manufacturer 2)To scrap Oil Cooling Unit (this product), it is required to have of main machine and end user CFC recovered (at cost to you) by a Type-1 CFC recovery agent registered by prefectural and city governments. 3The "progression management system (system to control the commission and transfer of CFC in writing) " was introduced on October 1, 2007. When Oil Cooling Unit is scrapped, it is stipulated to manage the process of transfer of CFC in writing so as to carry out the thorough recovery of CFC. There is no need to manage the maintenance (servicing, repairs) of Oil Cooling Unit in writing. Note) As for a product (Oil Cooling Unit) currently being used by an end user, there is no need to attach a caution plate (label) shown below according to the Law Concerning the Recovery and Destruction of Fluorocarbons. Obligation for product as the manufacturer Obligation: To attach a caution plate (label) according to the of Oil Cooling Unit (Daikin Industries) Law Concerning the Recovery and Destruction of Fluorocarbons OProvide information regarding the Law Concerning the Recovery PR activities as the manufacturer of Oil Cooling Unit and Destruction of Fluorocarbons in specification sheets and brochures of Oil Cooling Unit so as to keep customers informed (Daikin Industries)

The overview of the Daikin CFC recovery system and information on the overall contact counter (Daikin Contact Center) is given below. Daikin recovers CFC from a Type 1 specified product not only of Daikin's products, but also those of other manufacturers. Contact the Daikin Contact Center shown below for CFC recovery.

of the obligation of compliance with the Law.

Overview of Daikin CFC recovery (destruction) system

- O First contact Daikin Contact Center.
- O Daikin has a nationwide system of refrigerant recovery teams (about 500 teams in the Daikin Group). The team visits the site of Oil Cooling Unit to be scrapped at reasonable dispatch expenses. You don't have to pay
- The procedure follows steps 1 through 6 as shown below.




- Note) After recovering CFC, the Oil Cooling Unit (product) itself should be scrapped by yourself as was the case in the past. (Daikin is not engaged in scrapping and disposing of the equipment body.)
 - CFC recovery (destruction) is conducted on a chargeable basis. Please contact the Daikin Contact Center for details.

AKZI8 series | Example of basic installation onto tank

Notes for manufacturing of tank


- 1.Separate the liquid tank into at least three sections. Use the over-flow system and take measures so that foreign matter such as cutting powder and debris do not get directly into the suction line.
- 2.Arrange and locate the partition plates and piping position properly so that high-temperature liquid returned from the main machine and low-temperature liquid cooled by Oil Cooling Unit are evenly mixed.
- 3. Design the tank so that the tank inside can be cleaned with ease (For instance, the tank upper plate can be removed).
- 4.Tank material ... The use of SUS is recommended for the tank material and adequate consideration should be given to the compatibility of the tank material with cooling liquid.

(For instance, SS may be used as the tank material in combined use with coating (epoxy resin) inside the tank for grinding liquid.)



Separate installation type

When the tank depth is less than the dimension "H" shown in the diagram above



- Note) 1. If it is expected that cooling powder and debris will get into the tank, install efficient filters in the supply or return line.
 - 2. If foreign matter such as cutting powder and debris deposit and adhere onto the cooling coil, the cooling capacity is reduced and failure may result

erning the Reco

expensive costs (for packaging, loading, transportation, etc.) to send Oil Cooling Unit back to us.

Specific obligations and measures to be taken

Horsepower | Cooling capacity

Sales starting time

Discontinuation time

10,000

9,500

AKS303K AKS303AK

 $\Diamond \longrightarrow \Diamond$

'88.1~10

'93.3

In addition, a model having the last alphabetic characters "AK" is newer than a model ending with "K" only. (For instance, AKS35AK is

'98.12

'02.3

'88

'97.3

'02.9

2. The cooling capacity is represented by the value at the standard point and at 60 Hz for all models.

'87

'88

3. The dimensions of the equipment may be changed on a newer type and older type on some models. Please check the dimensions on the brochure and specification sheet (outline drawing) for selecting your equipment. When you are about to buy new equipment due to a failure of the equipment or for other reasons, please check the conditions of new

equipment and select an appropriate type. 4. All the models have been changed to the inverter type since 2002.

'86

'88

ON-OFF type

'87.5

'02.3

'87.5

5. AKSZ(S) "7" series uses new refrigerant R407C, AKSZ(S) "8" series uses new refrigerant R410A, and all other models use R22.

6. *7 Existing machines of 1HP class (AKS105AK, AKZ(S) 257 class) were integrated into AKZ328 of 1.2HP class.

Supporting information

New

AKZ908

AKZ306 AKZ(S)907

'96.8~10 | '01.10~'02.2 | '02~'03


'05.3

Inverter type



Table of History of Oil Cooling Unit for cutting and grinding oil (liquid) (Immersion type)

AKJ→AKZ



Note) 1. The larger the last number of a model name, the newer the series (For instance, AKZJ358 is newer than AKZJ357)

2. The cooling capacity is represented by the value at the standard point and at 60 Hz for all models

3. The dimensions of the equipment may be changed on a newer type and older type on some models. Please check the dimensions on the brochure and specification sheet (outline drawing) for selecting your equipment. When you are about to buy new equipment due to a failure of the equipment or for other reasons, please check the conditions of new equipment and select appropriate equipment.

All the models have been changed to the inverter type since 2002.
 AKZJ "7" series uses new refrigerant R407C, AKZJ "8" series uses new refrigerant R410A, and all other models use R22.

6. *7 Existing machines of 1HP class (AKJ100AK, AKJ106, AKZJ287 class) were integrated into AKZJ328 of 1.2HP class.

speedy delivery and safety through a broad-based network in thirteen countries all throughout the world.



For servicing of Oil Cooling Unit in Japan, contact Daikin Contact Center.

The service network extending all throughout the country is ready to offer you speedy service.

The Center is open 24 hours a day, 365 days a year to respond to your inquiries and requests for servicing.

DAIKIN Contact Center

Overall Customer Counter

0120-14-9955.....Toll-free number from anywhere in Japan

For inquiries by facsimile 0120-84-1069..... Toll-free fax number West Japan Contact Center 4-5-2 Korai-bashi, Chuo-ku, Osaka-shi, Osaka 541-0043


Coffice hours

Open 24 hours a day, 365 days a year

Available service

Consultation and inquiries about repair parts and servicing of hydraulic equipment

Consultation and inquiries about recovery of CFC



Supporting information



Overseas Service Network

Please contact Daikin Sales Counter for servicing of Oil Cooling Unit in countries outside Japan. Eighteen sales agents of the Air-conditioning and Hydraulic Division of Daikin are located in thirteen countries as listed below and are ready to offer you service.

Country/Region		Company name	Address	
		大金空調技術 (北京) 有限公司 DAIKIN AIR CONDITIONING TECHNOLOGY (BEIJING) CO.,LTD.	北京市東城区長安街1号東方広場 東方経貿城東三弁公楼20屋 20F, TOWER E3, ORIENTAL PLAZA, NO.1 EAST CHANG AN AVE DONG CHENG DISTRICT, BEIJING	
C	China	大金空調技術 (上海) 有限公司 DAIKIN AIR CONDITIONING TECHNOLOGY (SHANGHAI) CO.,LTD.	上海市南京西路1468号 中欣大厦B1 UNITED PLAZA B1, 1468 NAN JING RD (W), SHANGHAI	
		大金空調技術 (広州) 有限公司 DAIKIN AIR CONDITIONING TECHNOLOGY (GUANGZHOU) CO.,LTD.	広州市天河体育西路123号新創挙大厦18階A室 A 18/F, XINCHUANGJU BUILDING, NO.123 TIYUXI ROAD, TIANHE GUANGZHOU CHINA	
		◎大金工業株式会社 上海事務所 液圧控制課 DAIKIN SHANGHAI OFFICE OIL-HYDRAULICS DIV.	上海市南京西路1468号中欣大厦606室 RM.606,1468 NAN JING RD(W) SHANGHAI CHINA	
Hor	ng Kong	DAIKIN AIR CONDITIONING (HONG KONG) LTD.	17/F,FUTURA PLAZA,111-113 HOW MING STREET, KWUN TONG, KOWLOON	
Korea		⊚KD HYDRAULICS,LTD.	1ST FLOOR,DONGIL BLDG,242,2-KA. YOUNGDUNGPO-DONG,YOUNGDUNGPO-KU, SEOUL KOREA	
_	olwon	HO TAI DEVELOPMENT CO.,LTD.	161 TUNG-YI STREET,TAI-SHAN HSIANG, TAIPEI HSIEN,TAIWAN	
13	aiwan	©TAICIN ENTERPRISE	NO.67 KAI AN 2 STREET AN NAN CHIU TAINAN, TAIWAN	
Sin	gapore	DAIKIN ASIA SERVICING PTE. LTD.	19 LOYANG WAY #02-21 SINGAPORE 508724	
Th	nailand	SIAM DAIKIN SALES CO., LTD.	49/9 MOO 5, SOI ONNUCH 55/1 (SIAM DAIKIN) ONNUCH RD, K.M.7.5, PRAVET SUBDISTRICT, PRAVET DISTRICT, BANGKOK 10250, THAILAND	
I	ndia	DAIKIN AIR CONDITIONING INDIA PVT.LTD DELHI BRANCH	F25/2, OKHLA INDUSTRIAL AREA, PHASE II NEW DELHI 110020	
	Italy	DAIKIN AIR CONDITIONING ITALY S.P.A.	VIA MILANO, 6, 20097 SAN DONATO MILANESE	
Euro	France	DAIKIN AIR CONDITIONING FRANCF SA	LE CAPITOLE 55, AVENUE DES CHAMPS PIERREUX 92012 NANTERRE CEDEX, FRANCE	
ope	Spain	DAIKIN AIR CONDITIONING SPAIN S.A.	CALLE LABASTIDA 2 28034, MADRID, SPAIN	
	UK	DAIKIN AIR CONDITIONING UK., LTD.	1 RIVER COURT, ALBERT DRIVE WOKING, SURREY, GU21 5RP	
Au	stralia	DAIKIN AUSTRALIA (PTY) LTD.	77-83 ALFRED ROAD, CHIPPING NORTON, N.S.W. 2170, AUSTRALIA	
	U.S.	○ALL WORLD MACHINERY	1301 W.DIGGINS HARVARD IL 60033,USA	

 \bigcirc Sales agents of hydraulic equipment.

Others are the sales agent of air conditioning equipment.

Note) Contact the Daikin Contact Center given on the back page for servicing in Japan.

(30 As of July 31, 2006.)